WATER SUPPLY DIVISION.

Dated 7th August 1931.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Water Supply Division, up to 24th August 1931, for fixing Sanitary Fittings and drainage arrangement to the State New Insurance Office Building, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of October 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Water Supply Division, between the hours of 11 A.M. to 5 P.M. on other days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, shewing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 130 in cash as earnest money, and be subscribed "Tender for fixing Sanitary Fittings and drainage arrangements to the State New Insurance Office Building, Bangalore," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

Items of work for providing sanitary fittings and drainage arrangements to the "State Insurance New Office," Bangalore.

No.	Items of work	Unit	Quantity
1	Fixing Ul. C. with fittings, etc., complete and including cost of concrete filling at the Hindustani closets.	No.	4
2	Fixing urinal sets as per above	„	4
3	Fixing lavatory basin complete with fixing mirror and Towel rail	„	1
4	Fixing cast iron pipes including cutting and lead jointing and with necessary clamps.	R.ft.	120
5	Fixing cast iron specials such as bends offsets, etc., with lead jointing complete.	No.	20
6	Providing and fixing 3" cast iron pipes with lead joints including cost of pipes bends or junctions as per requirements.	R.ft.	80
7	Providing and fixing 3" lead pipes with wiped solder joints and brass socket and ferrule, etc., complete.	„	30
8	Providing and fixing 2" cast iron pipes with bends or junctions as per requirements.	„	60
9	Boring holes in walls of stone masonry and redoing with cement mortar masonry.	No.	12
10	Boring holes in big cornices and redoing	„	12
11	Do in small cornices and redoing	„	12
12	Providing and fixing ornamental ame cowls to 4" and 3" pipes ...	„	12
13	Constructing gully trap cisterns including cost of hinged lid and frame 14" x 12".	„	4
14	Constructing ordinary cisterns and providing 10" x 10" C. I. gratings and fixing.	„	2
15	Boring holes in terrace and redoing	„	2
16	Laying and bending 2" lead pipe including cost of fixing brass socket and tail piece for each closet.	„	4
17	Constructing partition walls of 4½" half brick thickness with and metal and brick in cement mortar masonry of about 4' x 7' each including coping on the top.	„	8
18	Cement concrete bed of 3" below white glazed tiled flooring ...	Sqr.	4
19	Fixing milk white glazed tiles for floor and walls including cost of fixing curved tiles cornice tiles, etc., complete and making ground sinks and pointing with white cement.	„	7

No.	Items of work	Unit	Quantity
20	Providing teakwood screen with doors at lavatory compartments as per design of Ul. C. enclosure at the Legislative Council Hall bath rooms complete with nickel plated spring hinges to doors yale locks etc., with white enamelled painting inside and polishing outside.	S.ft.	250
21	Providing and laying and jointing $\frac{3}{4}$" galvanized pipes including cost of fittings cutting and threading and grooving walls or floor and redoing.	R.ft.	200
22	Fixing $1\frac{1}{2}$" lead pipes with wiped solder joints to lavatory waste ...	No.	4
23	Providing $\frac{1}{2}$" and $\frac{3}{4}$" lead pipes and fixing with wiped solder joints, etc., complete.	"	16
	Drainage arrangements.		
1	Earthwork excavation for pipe trenches including fitting trenches watering and tamping and removal of surplus earth.	C.yd.	325
2	Laying and jointing stone ware pipes of approved quantity with cement mortar including cost of pipes—		
	(*a*) 4" pipe line	R.ft.	60
	(*b*) 6" pipe line	"	720
3	Constructing square manholes up to 5' depth with earthwork excavation 9" brick walls 9" surki concrete bed construction of inside drains cement plastering and providing and fixing 21" C. I. manhole cover and frame and steps where required.	No.	5

B. R. GARUDACHAR,
Executive Engineer.

KOLAR DIVISION.

Dated 1st August 1931.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division up to 2 P.M., 21st August 1931, for restoring the Breached Byatarayanahalli Devarakere Minor Tank, Regd. No. 193 of Malur Taluk, Kolar District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 30th June 1932.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. to 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees one hundred and eighty (Rs. 180) only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring the Breached Byatarayanahalli, Devarakere Minor Tank, Regd. No. 193 of Malur Taluk, Kolar District" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of the work both in words and figures.

10. The tenders stating that the work would be executed at a certain percentage in excess or lower than the estimated rates will not be accepted.